Bruhat Bangalore Mahanagara Palike
Executive Engineer Dasarahalli Division

Name of Work:Development of park and Construction of Watchmen room at Bagalgunte 13th cross, Nagalakshmi Temple Park in Dasarahalli Zone, Ward No.14

Modified Schedule - B

Sl No	Description of Item	Unit	Quantity	Rate, Rs	
				In Figures	In Words
1	Geophysical investigation at site for sinking borewells for supplying drinking water to the habitation either through the Hand Pump MWS or P.W.S.S. by vertical electrical sounding by adopting Venner or Schlumbergers's method, including reconnaissance survey of geological formation, Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 10 meter in consolidated formation for proper seating of casing pipe,depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information requiredincluding transportation of instruments and accessories to work site, engaging technical personal and labour required etc. NOTE: 1) Additional rate on Item 1&2 is allowed for drilling in over burden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a) Above 20 M and upto 30 M - 15%, b) Above 30 M - 30% (Measurement of overburden is restricted to the depth of casing pipe fixed excluding initial depth of 20M and projection above	NOS	0.00	3760.00	Rupees Three Thousand Seven Hundred Sixty Only
2	Sinking borewell of 165 mm dia. clear, using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF and above, in all strata of earth, including over burden upto 20M, fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicles, crew charges, cost of consumables, cost of yield test at the final depth with a minimum working of compressor for one hour etc. complete. The cost excludes the cost of casing pipes, collars and caps etc.) for: (Page no-xx, Item No-13.01-(a),PRED RWS SR 2019-20.Ammendment GO no RDWSSD 27 RWS(4) 2019 Dated 02.05-2019) ---- All terms and conditions are as per tender document	Mtrs	0.00	345.00	Rupees Three Hundred Forty Five Only
3	Sinking borewell of 165 mm dia. clear, using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF and above, in all strata of earth, including over burden upto 20M, fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicles, crew charges, cost of consumables, cost of yield test at the final depth with a minimum working of compressor for one hour etc. complete. The cost excludes the cost of casing pipes, collars and caps etc.) for: (Page no-xx, Item No-13.01(b),PRED RWS SR 2019-20.Ammendment GO no RDWSSD 27 RWS(4) 2019 Dated 02.05-2019) ---- All terms and conditions are as per tender document	Mtrs	0.00	440.00	Rupees Four Hundred Forty Only
4	Sinking borewell of 165 mm dia. clear, using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF and above, in all strata of earth, including over burden upto 20M, fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicles, crew charges, cost of consumables, cost of yield test at the final depth with a minimum working of compressor for one hour etc. complete. The cost excludes the cost of casing pipes, collars and caps etc.) for: (Page no-xx, Item No-13.01(c),PRED RWS SR 2019-20.Ammendment GO no RDWSSD 27 RWS(4) 2019 Dated 02.05-2019) ---- All terms and conditions are as per tender document	Mtrs	0.00	450.00	Rupees Four Hundred Fifty Only
5	Sinking borewell of 165 mm dia. clear, using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF and above, in all strata of earth, including over burden upto 20M, fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicles, crew charges, cost of consumables, cost of yield test at the final depth with a minimum working of compressor for one hour etc. complete. The cost excludes the cost of casing pipes, collars and caps etc.) for: (Page no-xx, Item No-13.01(d),PRED RWS SR 2019-20.Ammendment GO no RDWSSD 27 RWS(4) 2019 Dated 02.05-2019) ---- All terms and conditions are as per	Mtrs	0.00	530.00	Rupees Five Hundred Thirty Only

Scanned with CamScann

	~~Sinking borewell of 165 mm dia. clear, using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF and above, in all strata of earth, including over burden upto 20M, fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicles, crew charges, cost of consumables, cost of yield test at the final depth with a minimum working of compressor for one hour etc. complete. The cost excludes the cost of casing pipes, collars and caps etc.) for: (Page no-xx, Item No-13.01(e),PRED RWS SR 2019-20,Ammendment GO no RDWSSD 27 RWS(4) 2019 Dated 02.05-2019) ---- All terms and conditions are as per~~	Mtrs	0.00	632.00	Rupees Six Hundred Thirty Two Only
7	Sinking borewell of 165 mm dia. clear, using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF and above, in all strata of earth, including over burden upto 20M, fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicles, crew charges, cost of consumables, cost of yield test at the final depth with a minimum working of compressor for one hour etc. complete. The cost excludes the cost of casing pipes, collars and caps etc.) for: (Page no-xx, Item No-13.01(f),PRED RWS SR 2019-20,Ammendment GO no RDWSSD 27 RWS(4) 2019 Dated 02.05-2019) ---- All terms and conditions are as per tender document	Mtrs	0.00	698.00	Rupees Six Hundred Ninety Eight Only
8	Sinking borewell of 165 mm dia. clear, using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF and above, in all strata of earth, including over burden upto 20M, fixing of casing pipes, collars and cap with necessary	Mtrs	0.00	821.00	Rupees Eight Hundred Twenty One Only
9	Supply of ISI mark 175 mm nominal Bore, plain end steel casing pipe grade of steel Fe 410 of wall thickness 5.4 mm thick confirming to IS 4270:2001 and latest amendments, electric, resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5 to 7 mts. both ends threaded confirming to IS 554/1985 one end fixedwith socket confirming to IS 4270:2001 and the other end with screwd pipes. All Pipe Shall be reasonably free from defects. the tubesshall be reasonably straigth should be with ISI marking, weighing, 25.1 kg/mtr (inclusive of all taxes duties) prices include collar - medium duty(Page no-III, Item No-84 (Material Components of PRE .Circle Bangalore SR 2012-13.)`from 0.00 m to 20m ---- All terms and conditions are as per tender document	m	0.00	1325.00	Rupees One Thousand Three Hundred Twenty Five Only
10	20to 30mtrs ---- All terms and conditions are as per tender document	m	0.00	1520.00	Rupees One Thousand Five Hundred Twenty Only
11	Supply of 175 MM MS CAP (Page no-III, Item No-85 (Material Components of PRE .Circle Bangalore SR 2012-13.)` ---- All terms and conditions are as per tender document	Each	0.00	100.00	Rupees One Hundred Only
12	Supplying, Erection and commissioning of 5HP/3.7 kw 12 stage Submersible pump of Approved make with ISI mark including necessary accessories (Page no-XLI, Item No-6 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Each	0.00	31420.00	Rupees Thirty One Thousand Four Hundred Twenty Only
13	Supplying and drawing 3 core flat PVC Sheathed Submersible pump cable manufactured with electrolytic grade copper wityh flexible copper with low resistance conductor confirming to table 3 class 5 of IS 8130 -1984 and virgin grade PVC insulation and power coating extruded PVC Sheathed Suitable for working voltage up to 1100 volts as per IS 694:1990 & confirming to GTP of GROUP-A -3C X 2.5Sqmm. (Page no-7, Item No-2.6.2 of Electrical PWD SR 2019-20.) ---- All terms and conditions are as per tender document	Mtr	0.00	98.00	Rupees Ninety Eight Only
14	KSRB13-9.3 : Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure of outside diameter raising mains & exposed distribution pipes with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM and testing complete as per specifications. Specification No.KBS 13.2.15.2 / 13.9 -50mm dia (Page no-96, Item No-13.73.1 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	m	0.00	353.00	Rupees Three Hundred Fifty Three Only
15	KSRB 13-7.1-4: Providing and fixing in position nominal bore Gun-metal non return valve horizontal type of approved make including cost of all materials, labour and HOM with all leads complete as per specifications.Specification No KBS 13.2.10/13.13-50mm dianominal bore (Page no-95, Item No-13.55 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	No	0.00	1435.00	Rupees One Thousand Four Hundred Thirty Five Only
16	KSRB 13-7.1-4: Providing and fixing in position nominal bore Gun-metal non return valve horizontal type of approved make including cost of all materials, labour and HOM with all leads complete as per specifications.Specification No KBS 13.2.10/13.13-50mm dianominal bore (Page no-95, Item No-13.55 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	No	0.00	6400.00	Rupees Six Thousand Four Hundred Only

Scanned with CamScann

	Supplying, fixing and wiring Electronic Trivector Meter (ETV) 5 to 32/63 Amps Class Polyphase 4 wire whole current class-1 Accuracy Energy Meter.(Page no-29, Item No-5.35 of Electrical PWD SR 2019-20.) ---- All terms and conditions are as per tender document	EACH	0.00	4740.00	Rupees Four Thousand Seven Hundred Forty Only
	KSRB 2-2.1 : Earthwork excavation by manual means for foundation of buildings, water supply, sanitary lines and electrical conduits etc., either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.-In ordinary soil NO KBS 2.1(a)/2.3.5 (Page no-6, Item No-2.3 of PWD SR 2018-19.) ---- All	Cum	89.22	322.00	Rupees Three Hundred Twenty Two Only
19	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 OPC cement @ 180 Kgs with 40mm and down size graded granite metal of coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, machine mixed,concrete laid in layers not exceeding 15cms thick, well compacted in foundation including cost of all materials, labour, HOM curing complete as per Specification No. KBS 4.1, 4.2 (Page no-13, Item No-4.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	16.73	5510.00	Rupees Five Thousand Five Hundred Ten Only
20	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar, stone hammerd dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13-cement morter 1:6 (Page no-25, Item No-5.6 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	55.79	4960.00	Rupees Four Thousand Nine Hundred Sixty Only
21	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6,edges of stones chistle dressed in courses not less than 15 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (Page no-25, Item No-5.9 of PWD SR 2018-19.) ---- All terms and	Cum	50.57	5920.00	Rupees Five Thousand Nine Hundred Twenty Only
22	KSRB 4-2.2: Providing and laying in position Reinforced Cement Concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal of coarse aggregates @ 0.69 cum and fine aggregates @ 0.46 cum, with superplastisiser @ 3 Liters conforming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation for footing ,pedastals,retaining walls,return walls, walls (any thickness) including attached pilasters, columnspillars,post struts, buttresses, bed blocks, anchor blocks & Plinths etc., including cost of all materials, labour, HOM curing complete as per Specifications Specification No. KBS 4.1, 4.6(Page no-14, Item No-4.11 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	7.32	6110.00	Rupees Six Thousand One Hundred Ten Only
23	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string	sqm	0.00	380.00	Rupees Three Hundred Eighty Only
24	KSRB 4.9.2 : Providing TMT Steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per Specifications. Specification No. KBS 4.6.3 -TMT bars Fe 500(Page no-18, Item No-4.46.2 of PWD SR 2018-19.) ---- All terms and	tonne	0.00	80150.00	Rupees Eighty Thousand One Hundred Fifty Only
25	KSRB : 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specification. Specification No. KBS 2.9 (Page no-7, Item No-2.10 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	46.51	215.00	Rupees Two Hundred Fifteen Only
	Above 125%	Cum	25.98	215.00	Rupees Two Hundred Fifteen Only
26	KSRB 15-3 : Providing 18mm thick cement plaster in single coat with cement mortar to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of	Sqm	0.00	263.00	Rupees Two Hundred Sixty Three Only
27	KSRB 15.1.2 Providing flush pointing 20mm deep to square rubble, course or uncoursed stone masonry with cement mortar after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.cement morter 1:4 (Page no-115, Item No-15.2 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	136.89	150.00	Rupees One Hundred Fifty Only
8	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications-With Primer (Page no-120, Item No-	Sqm	0.00	109.00	Rupees One Hundred Nine Only

Scanned with CamScann

	Applying and fixing M.S. Rectangular poles made out of 2 equal angles of 25x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) including cost of materials,labour,HOM complete asper specifications.(Page no-266, Item No-37.2 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	m	96.00	925.00	Rupees Nine Hundred Twenty Five Only
30	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint.including cost of materials,Labour HOM Complete as per Specification. (Page no-266, Item No-37.4 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	m	0.00	440.00	Rupees Four Hundred Forty Only
31	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint including cost of materials,Labour HOM Complete as per Specification (Page no-266, Item No-37.3 of PWD SR 2018-19.) ---- All	Sqm	0.00	770.00	Rupees Seven Hundred Seventy Only
32	Fabricating, providing and erecting in poiston of M S Ornamental security Grill Gate without hot dip using 75 x 12mm M S Flat for alround frame work with verticals at the centre and horizontal centere support M S Square of 20 x20 mm of different heights as shown in the drawing are to be fixed at 16 cms C/C for suqare bars of full height and at 8cms C / C for bottom rods providg ornamental C I Designers at the botom and C I arrows inthe midle and top. The entire frame work is to be fixed by means of expansion bolts to the brick pillars with necesary drillling holes. the work includes providng two coats of enamel painting over one coatr of red lead ready mix primer coat etc complete cost of all labour, painting, erection charges using hoist pulleycranes with all lead and lift, loading, transporting and unloading using hoist pulley cranes, scaffolding charges and all other incidental charges required for successful completion fo the work as per specification and drawings (Page no-	Sqm	0.00	142.00	Rupees One Hundred Forty Two Only
33	KSRB 24-13 : Removing the old paint from steel and / or other metal surface with hand scraping and making surface even including cost of labour, complete as per specifications. Specification No.KBS. (Page no-131, Item No-16.8 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender	Sqm	0.00	90.00	Rupees Ninety Only
34	KSRB 15-18.1 : Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications. (Page no-123, Item No-15.73 of PWD SR 2018-19.) ---- All terms	Sqm	0.00	44.00	Rupees Forty Four Only
35	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications(Page no-123, Item No-15.74 of PWD SR 2018-19.)` ---- All terms and conditions are as	Sqm	0.00	101.00	Rupees One Hundred One Only
36	KSRB 2-2.1 : Earthwork excavation by manual means for foundation of buildings, water supply, sanitary lines and electrical conduits etc., either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.-in ordinary	Cum	53.96	322.00	Rupees Three Hundred Twenty Two Only
	Above 125%	Cum	110.76	322.00	Rupees Three Hundred Twenty Two Only
37	kSRB-3.2: Providing and injecting chemical emulsion for Pre-constructional Anti-Termite Treatment, creating continuous chemical barrier under and around the column pits, walls, trenches, basement excavation, top surface of the plinth filling, junction of wall and floor, along the external perimeter of building, expansion joints, over the top surface of consolidated earth on which apron is to be laid, surrounding of pipes and conduits, with chloropyriphos emulsifiable concentrates of 20% concentration at 3.19 liter/sqm., including cost of chemical, diluting in water to one percent concentration, labour, HOM complete as per specifications. (Plinth area of the building at ground floor only shall be measured) Specification No. KBS : 3.2.6 / 3.2.7(Page no-10, Item No-3.2 of PWD SR 2018-19.) ---- All terms and conditions are as per tender	sqm	34.51	113.00	Rupees One Hundred Thirteen Only
	Above 125%	Sqm	201.11	113.00	Rupees One Hundred Thirteen Only

Scanned with CamScanner

	4.1.3: Providing and laying in position plain cement concrete of mix OPC cement @ 180 Kgs with 40mm and down size graded granite metal rse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted in foundation including cost of all materials, labour, HOM curing complete as per Specification No. KBS 4.1, 4.2 (Page no-13, Item No-4.3 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	cum	0.00	5500.00	Rupees Five Thousand Five Hundred Only
39	KSRB 4-2.2: Providing and laying in position Reinforced Cement Concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal of coarse aggregates @ 0.69 cum and fine aggregates @ 0.46 cum, with superplastisiser @ 3 Liters conforming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation for footing ,pedastals,retaining walls,return walls, walls (any thickness) including attached pilasters, columnspillars,post struts, buttresses, bed blocks, anchor blocks & Plinths etc., including cost of all materials, labour, HOM curing complete as per Specifications Specification No. KBS 4.1, 4.6(Page no-14, Item No-4.11 of PWD	Cum	16.11	6107.00	Rupees Six Thousand One Hundred Seven Only
	Above 125%	Cum	38.27	6107.00	Rupees Six Thousand One Hundred Seven Only
40	KSRB 4-2.8: Providing and laying in position Reinforced Cement Concrete of design mix M20 with OPC @ 320 Kgs with 20mm and down size graded granite metal of coarse aggregates @ 0.69 cum and fine aggregates @ 0.46 cum, with super plasticizer @ 3 Ltrs confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in Ground floor level for roof slabs, staircase ,lintels, and beams retaining walls,return walls, walls (any thickness)including attached pilesters,columns pillers,posts,struts,buttresses,string or lacing courses,parapets,coping ,bed blocks, anchor blocks,plain window cills ,fillets etc., including cost of all materials, labour, HOM curing complete but excluding the cost of reinforcement as per Specifications. Specification No. KBS 4.1, 4.6 (Page no-14, Item No-4.13 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	6360.00	Rupees Six Thousand Three Hundred Sixty Only
41	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (Page no-16, Item No-4.28 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	275.00	Rupees Two Hundred Seventy Five Only
42	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for columns, pillars, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per Specifications. Specification No. KBS 4.6.2 (Page no-16, Item No-4.32 of PWD SR 2018-19.) ---- All terms and conditions are as per tender	sqm	0.00	491.00	Rupees Four Hundred Ninety One Only
43	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(Page no-16, Item No-4.31 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	385.00	Rupees Three Hundred Eighty Five Only
44	KSRB 4-6.7 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (Page no-17, Item No-4.34 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	314.00	Rupees Three Hundred Fourteen Only
45	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications for heights more than 3.50m from Ground level Specification No. KBS 4.6.2 -0 to 5mts (Page no-16, Item No-4.29.2 of PWD SR 2018-19.) ---- All terms and conditions are as per tender	Sqm	0.00	430.00	Rupees Four Hundred Thirty Only
46	KSRB 4-1.7: Providing and laying in position Plain cement Concrete of mix 1:3:6 with OPC @ 220kgs,with 20mm and downsize graded granite metal coarse aggregates @0.69 cum and Fine aggregates @ 0.56 cum,machine mixed,concre laid in layers not exceeding 15 cms thick, well compacted, in foundation, Plinth and cills, including cost of all materials labour,HOM curing complete as per Specifications. Specification No .KBS 4.1,4.2.(Page no-13, Item	Cum	0.00	5730.00	Rupees Five Thousand Seven Hundred Thirty Only

Scanned with CamScann

	KSRB 4-2.10: Providing and laying in position Reinforced Cement Concrete of [illegible] mix M20 with OPC @ 24Kgs with 12mm and down size graded granite metal coarse aggregates @ 0.05175 cum and fine aggregates @ 0.0345 cum, with super plasticizer @ 0.225 Ltrs, machine mixed, well compacted for Plain chajja of 7.5cms average thickness, upto ground floor level, including cost of all materials, labour, HOM curing complete but excluding cost of reinforcement as per Specifications. Specification No. KBS 4.1, 4.6(Page no-15, Item No-4.19 of PWD SR 2018-19.) ---- All terms and conditions are as per	Sq.m	0.00	474.00	Rupees Four Hundred Seventy Four Only
48	KSRB 4-6.10 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for chajja, corbels etc., including edges including cost of all materials, labour complete as per specification. Specification No. KBS 4.6.2 (Page no-17, Item No-4.37 of PWD SR 2018-19.) ----	Sq.m	0.00	348.00	Rupees Three Hundred Forty Eight Only
49	KSRB 4.2.12 : Extra for providing throating or drip moulding to R.C.C. chajja with plastering (labour charges only) as per specifications. Specification No.KBS (Page no-15, Item No-4.21 of PWD SR 2018-19.) ---- All terms and	m	0.00	35.00	Rupees Thirty Five Only
50	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar, stone hammered dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13-cement mortar 1:6 (Page no-25, Item No-5.6 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	4960.00	Rupees Four Thousand Nine Hundred Sixty Only
51	KSRB : 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specification. Specification No. KBS 2.9 (Page no-7, Item No-2.10 of PWD SR 2018-19.) ----	Cum	0.00	215.00	Rupees Two Hundred Fifteen Only
52	KSRB 4.9.2 : Providing TMT Steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per Specifications. Specification No. KBS 4.6.3 -TMT bars Fe 500(Page no-18, Item No-4.46.2 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Tonne	0.00	84240.00	Rupees Eighty Four Thousand Two Hundred Forty Only
53	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1) : 2005 and constructed with CM 1: 4,as per IS 2572:2005 including cost of all materials labour Charges ,Scaffolding,curing,hire charges of all materials labour charges, scaffolding,curing,hire charges of machineries etc.,complete as per specifications.KBS No. 5.4 - with solid concrete blocks of size 400X200X200 (Page no-27, Item No-5.26.1 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Sqm	0.00	1035.00	Rupees One Thousand Thirty Five Only
54	KSRB 5-15 Providing and constructing non load bearing wall with solid concrete blocks of sizes 400 X 100 x 200mm having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (part 1) : 2005 and constructed with CM 1:4 as per IS 2572: 2005 including cost of all materials labour Charges, Scaffolding,curing,hire charges of machineries etc.,Complete as per secifications.KBS No 5.4(Page no-27, Item No-5.28 of PWD SR 2018-19.) ---- All	Sqm	0.00	875.00	Rupees Eight Hundred Seventy Five Only
55	KSRB 9.4-3 : Providing wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM complete as per specifications. Specification No. KBS 9.33-Mathi/Nandi Wood Frames (Page no-53, Item No-9.12 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Cum	0.00	79050.00	Rupees Seventy Nine Thousand Fifty Only
56	KSRB 9-27.1 : Fixing of frames in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debris with lead upto 50 m. including cost of materials, labour charges, complete as per specifications.- Fixing of door Frame. (Page no-60, Item No-9.80 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Nos	0.00	1475.00	Rupees One Thousand Four Hundred Seventy Five Only
57	KSRB 9-9.1: Providing and fixing flush door shutter made out of solid core black board type ,well seasoned chemically treated hard wood battens and internal frame with minimum 45mm wide wooden frame all round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (part-1)1991 from manufacturer(factory) complete as per specification. -30mm thick both side teak. (Page no-65, Item No-9.106.1 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender	Sqm	0.00	3990.00	Rupees Three Thousand Nine Hundred Ninety Only

Scanned with CamScanner

	PVC DOOR FRAME Providing & fixing factory made PVC Door frame of 150x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2 No.s of 150mm long brackets of 15x15mm M.S Square tube, the entire door frame to be reinforced with 19x19mm M.S Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size complete as per manufacturers specification & direction of Engineer-in-charge. (Page no-60, Item No-9.84 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	505.00	Rupees Five Hundred Five Only
59	PVC DOOR SHUTTER (Nandi or Equivalent) Supply and fixing of door shuttersmade of rigid PVC extruded hollow section (Nandi or equivalent) o f 20mm x 200mm with the wall thickness of 1.0mm + /0.1mm equally divided into 4nos with tongue and groove locking arrangements. The shutter frame is made of 58x24 mm with the wall thickness of 1.5mm+/ -0.15mm section metricut and joined at 4 corners with 125mmx225mm plastic brackets. The shutter shall be horizontally reinforced with 2nos of 8mm PVC rods. Teak wood battons shall be reinforced inside the door shutter during the fabrication of the door shutter at those points wherever the hardware is fixed on to the door shutter. (Page no-61, Item No-9.86 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	1925.00	Rupees One Thousand Nine Hundred Twenty Five Only
60	KSRB 7.10 : Providing and fixing in position aluminum windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 61.85x31.75mm. with 1.2mm thick, bottom section weight 0.695 kg/m, sides and top sections 1.3 mm. thick weight 0.659 kg/m; and shutter comprising top and bottom section of size 40mmx18mm, 1.25mm thick 0.417 kg./m; shutter outer side 40mmx18mm, 1.25mm.thick weight 0.417 kg/m, shutter interlock section 40mmx26.7mm, 1.1mm thick, weight 0.469 kg/m. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminum handles tower bolts etc.; and providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading aluminum sections including cutting to required length, joints mitred	Sqm	0.00	4550.00	Rupees Four Thousand Five Hundred Fifty Only
61	KSRB 7.9 : Providing and fixing M.S.grill work for windows and ventilators using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM complete as per Specifications. specification No. KBS 7.12 (Page no-34, Item No-7.9 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Kg	0.00	102.00	Rupees One Hundred Two Only
62	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications(Page no-123, Item No-15.74 of PWD SR 2018-19.)` ---- All terms and conditions are as	Sqm	0.00	100.00	Rupees One Hundred Only
63	Aldrop (door lock) (Page no-XV, Item No-Sl.No .386, Code no 0134 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Each	0.00	360.00	Rupees Three Hundred Sixty Only
64	Tower Bolt 300 mm long (Page no-XVI, Sl.No .407, Code no 0427 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Each	0.00	107.00	Rupees One Hundred Seven Only
65	Hinges 5" HEAVY DUTY (Page no-XV, Item No-Sl.No .390, Code no 0188 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Each	0.00	33.00	Rupees Thirty Three Only
66	Hold fasts MS (Page no-XV, Item No-Sl.No .391, Code no 0189 of PWD SR 2018-19.) ---- All terms and conditions are as per tender document	Each	0.00	34.00	Rupees Thirty Four Only
67	Handles Power coated 150mm (Page no-XV, Item No-Sl.No .388, Code no 0178 of PWD SR 2018-19.) ---- All terms and conditions are as per tender	Each	0.00	53.00	Rupees Fifty Three Only
68	screws 40mm(Page no-XVI, Item No-Sl.No .404, Code no 0384 of PWD SR 2018-	Each	0.00	2.50	Rupees Two And Paise Fifty Only
69	KSRB 15-3 : Providing 18mm thick cement plaster in single coat with cement mortar to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications -Cement Morter 1:6 (Page no-116, Item No-15.17 of PWD SR 2018-19.) ---- All terms and conditions	Sqm	0.00	264.00	Rupees Two Hundred Sixty Four Only
70	KSRB15-5.1 : Providing rough cement plastering 15mm thick in single coat with cement mortar to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications -cement mortar 1:4 (Page no-117, Item No-15.30 of PWD SR 2018-19.)` ---- All terms and	Sqm	0.00	220.00	Rupees Two Hundred Twenty Only
71	KSRB15-7 : Providing lime rendering for plastering to wall and ceiling , including cost of materials, labour, curing complete as per specifications.(Page no-117, Item No-15.33 of PWD SR 2018-19.)` ---- All terms and conditions are	Sqm	0.00	34.00	Rupees Thirty Four Only

Scanned with CamScanner

	...ting and fixing vitrified glazed tiles of approved make ,quality and colour ...600 X600X 10mm thick fixed on bed of 12mm thick cement mortar for ...ic skirting and jointed with neat cement slurry mixed with pigment to ...atch shade of tiles,including providing spacers at required interval and ...removing stains,including cost of all materials,mortar,labour,etc., Complete as ...per specification (Page no-109, Item No-14.45of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	970.00	Rupees Nine Hundred Seventy Only
73	KSRB 14.14-5: Providing Ceramic tiles of approved make,shade and size for flooring,treads of steps and landings laid on a bed of 12mm thick,cement mortar 1:3 mix flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications. Specification No.KBS-for Ceramic tiles of size 30 X30 cms 6mm thick. (Page no-108, Item No-14.36.2of PWD SR 2018-19.) ---- All terms and conditions are as	Sqm	0.00	1300.00	Rupees One Thousand Three Hundred Only
74	KSRB 14-17.2 : Providing skirting, dadoing, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Specification No.KBS 14.16, 14.17 -colour glazed tiles 30x45 cms 6mm thick with border of size 30 X10cms. (Page no-108, Item No-14.41.3 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	1375.00	Rupees One Thousand Three Hundred Seventy Five Only
75	KSRB 15-14.1 providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper, primer after thoroughly brooming the surface frame free from mortar drops and other forgive matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.(Page no-119, Item No-15.49.1 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	117.00	Rupees One Hundred Seventeen Only
76	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of all materials, cost of labour and scaffolding etc., complete as per the specification. (Page no-128, Item No-15.106 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	84.00	Rupees Eighty Four Only
77	KSRB 15-15.2 providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approveded shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per Specifications-With primer (Page no-119, Item No-15.51.2 of PWD SR 2018-19.)` ---- All terms and	Sqm	0.00	97.00	Rupees Ninety Seven Only
78	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications-With Primer (Page no-120, Item No-15.53.2 of PWD SR 2018-19.) ---- All terms and conditions are as per tender	Sqm	0.00	110.00	Rupees One Hundred Ten Only
79	KSRB 15-17.4 : Applying priming coat over new wood surface and / or wood based surface, after brushing with ready mix eanmel priming paint including preparing the surface after throughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications (Page no-121, Item No-15.58 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	54.00	Rupees Fifty Four Only
)	KSRB 15-17.6 : Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications. (Page no-121, Item No-15.60.1 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	104.00	Rupees One Hundred Four Only
	KSRB 10-3 : Providing and laying integral cement based waterproofing reatment including preparation of surface as required for treatment of roofs, alconies, terraces etc., consisting of following application. (a) Applying and outing a slurry coat of neat cement using 2.75 kg/sqm of cement admixed ith proprietary water proofing compound conforming to IS:2645 over the C slab after cleaning the surface before treatment. (b) Laying cement ncrete using broken brick bats 25mm to 100mm size with 50% of cement rtar 1:5 admixed with proprietary water proofing compound conforming 645 over 20mm thick layer of cement mortar 1:5 admixed with proprietary er proofing compound to required slope and treating similarly the ining walls upto 300mm height including rounding off junctions of walls slabs. (c) After two days of proper curing, applying a second coat of ent lurry admixed with proprietary water proofing compound (d) Finishing urface with 20mm thick jointless cement mortar of mix 1:4 admixed with ietary water proofing compound and finally finishing the surface with	Sqm	0.00	1085.00	Rupees One Thousand Eighty Five Only

Scanned with CamScann

Name of Work: Development of work and ...

	providing and laying plat form using prepolished, water cut / gang saw 40mm thick telephonic Black Granite, laid on existing vertical -supports and fixing in CM 1:3 proportion. Including cutting to required shape, pattern with paper joints, including full rounding for nosing, finished with cement mortar, pointed with colour pigments to match the colour of slab making through jointing with sealant, making holes 25mm x 12mm grooves in joints including curing. (Page no-110, Item No-14.52 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	3805.00	Rupees Three Thousand Eight Hundred Five Only
83	Providing and fixing M.S. Hand railing for Balcony with 50mm dia. M.S. hollow pipe of 14 gauge, welded to 20mmx20mm M.S. square rod placed vertically, spaced at 100mm at regular intervals of 600mm. These vertical rods laterally tied to 3 horizontal rods spaced at equal interval. These assembly is fixed to concrete by using expansion bolts and welding the same to reinforcement bars and making good the surface. All the joints and sections hould be cut to length, welded and grinded wherever necessary etc., complete . The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification and drawing. (Page no-44, Item No-7.35 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	3065.00	Rupees Three Thousand Sixty Five Only
84	KSRB 11-14.3 : Providing and fixing stainless steel kitchen sink of size 400x915mm bowl depth 160mm, with drain board, M.S / C.I brackets, stainless steel plug 40 mm, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. (Page no-84, Item No-12.38 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	6900.00	Rupees Six Thousand Nine Hundred Only
85	KSRB 14.9-2 : Providing and laying M-15 cement concrete flooring 60 mm thick with metallic concrete hardner toping, under layer of 45mm thick M-15 cement concrete using broken granite metal of 20mm and down size and top layer of 15mm thick metallic cement hardner consisting of mix 1:2 (1 cement hardner mix : 2 granite metal 10mm nominal size) by volume, with metalic hardening compound of approved quality mix in the ratio of 4:1 (4 part of cement = 1 part of metallic floor hardening compound of approved quality by wt) , including finishing, cost of materials, labour, curing, complete as per specifications. Specification No. KBS 14.4 (Page no-104, Item No-14.14 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	Sqm	0.00	755.00	Rupees Seven Hundred Fifty Five Only
86	KSRB 15.8.1 Providing and fixing plaster mesh 100mm wide manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls chipped for services, junction between RCC and brick walls including cost of materials, labour for fixing complete as per specifications. (length of mesh only be measured for payment) (Page no-117, Item No-15.34 of PWD SR 2018-19.)` ---- All terms and conditions are as per tender document	m	0.00	28.00	Rupees Twenty Eight Only
87	KSRB 11.50.3 450X450mm and 450mm depth (clear inside dimension) for single pipeline, using table mouled non- modular bricks of class designation 50 in cement mortor 1:5, CI cover with frame(light duty) 450x450mm(Page no-76, Item No-11.50.3 of PWD SR 2018-19) ---- All terms and conditions are as per tender document	m	0.00	5720.00	Rupees Five Thousand Seven Hundred Twenty Only
88	KSRB 11.50.2 600X610mm and 450mm depth (clear inside dimension) for single pipeline, using table mouled non- modular bricks of class designation 50 in cement mortor 1:5, CI cover with frame(light duty) 600x600mm (Page no-75, Item No-11.50.2 of PWD SR 2018-19) ---- All terms and conditions are as per tender document	m	0.00	9150.00	Rupees Nine Thousand One Hundred Fifty Only
89	KSRB13.8 : Providing and fixing to wall, ceiling and floor medium density polyethylene pipes 6.00 kgf/sq.cm working pressure of outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.1 / 13.9 for internal water supply connection (Page no-96, Item No-13.73.5 of PWD SR 2018-19) ---- All terms and conditions are as per tender document	m	0.00	642.00	Rupees Six Hundred Forty Two Only
	KSRB 11-5 : Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 1(Page no-79, Item No-12.5of PWD SR 2018-19) ---- All terms and conditions	Each	0.00	5352.00	Rupees Five Thousand Three Hundred Fifty Two Only

D. Anand

Scanned with CamScanner

	11-11.1 : Providing and fixing white vitreous china clay, flat back wash down pattern 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and including cost of materials, labour complete as per specifications. Specification No. KBS 11(Page no-82, Item No-12.23 of PWD SR 2018-19) ---- All terms and conditions are as per tender document	Each	0.00	4320.00	Rupees Four Thousand Three Hundred Twenty Only
92	KSRB 13-11.1 : Providing and placing on terrace, polyethylene water storage tanks as per IS 12701:1996 with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications.(For 1000 litre capacity) Specification No.KBS 13.22(Page no-96, Item No-19.783 of PWD SR 2018-19) -- All terms and conditions are as per tender document	Nos.	0.00	7355.00	Rupees Seven Thousand Three Hundred Fifty Five Only
93	KSRB13-6.1-2 : Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3 (Page no-93, Item No-13.27 of PWD SR 2018-19) ---- All terms and conditions are as per tender document	Nos.	0.00	150.00	Rupees One Hundred Fifty Only
94	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia. ---- All terms and conditions are as per tender document	Nos.	0.00	161.00	Rupees One Hundred Sixty One Only
95	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). - 10cms x 7.5cms ---- All terms and conditions are as per tender document	Each	0.00	270.00	Rupees Two Hundred Seventy Only
96	Providing stoneware gully trap of approved quality and make fixing in M-15 and plastering with CM 1:3 wherever necessary.(Rate includes cost of all materials, fixtures and lead).- 10cms x 10cms(Page no-90, Item No-12.112.1 of PWD SR 2018-19) ---- All terms and conditions are as per tender document	Each	0.00	205.00	Rupees Two Hundred Five Only
97	KSRB13-9.6 : Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure 90mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.2 / 13.9. (P.No. 96, I.No.13.73.4 of PWD SR 2018-19) ---- All terms and conditions are as per tender document	m	0.00	537.00	Rupees Five Hundred Thirty Seven Only
98	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 20mm nominal OD pipes(P.No. 98, I.No.13.85.2 of PWD SR 2018-19) ---- All terms and conditions are as per tender document	m	0.00	169.00	Rupees One Hundred Sixty Nine Only
99	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 25 mm nominal OD pipes(P.No. 98, I.No.13.85.3 of PWD SR 2018-19) ---- All terms and conditions are as per tender document	m	0.00	211.00	Rupees Two Hundred Eleven Only
100	Supplying heavy gauge PVC conduit pipe .....mm dia .....mm thick confirming to IS 2509 with suitable size bends, metal/PVC junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary(Page No -2, Item No 1.1.1, Electrical PWD SR 2019-20). ---- All terms and conditions are as per tender document	Mtr	0.00	50.00	Rupees Fifty Only
101	Supplying heavy gauge PVC conduit pipe .....dia .....mm thick confirming to IS 2509 with suitable size bends, junctionboxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws (Page No -2, Item No 1.1.1, Electrical PWD SR 2019-20). ---- All terms and conditions are as per tender document	Mtr	0.00	65.00	Rupees Sixty Five Only
102	Supplying and fixing PVC/metal conduit Deep junction box (Page No -3, Item No 1.5.1, Electrical PWD SR 2019-20). ---- All terms and conditions are as per tender document	No	0.00	43.00	Rupees Forty Three Only

Scanned with CamScann

	...for groove cutting in brick wall/CC floor to the suitable depth for ...ing of conduit/GI pipe and plastering, finishing upto wall surface ...e (Page No -3, Item No 3.2.1, Electrical PWD SR 2019-20) ---- All terms ...conditions are as per tender document	Mtr	0.00	21.00	Rupees Twenty One Only
	...ing And Fixing Metal Fan Box with Round Hook (Page No -3, Item No ...3.1.5, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	No	0.00	85.00	Rupees Eighty Five Only
105	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0 sqmm (Earth wire) FRLS multi strand PVC insulated copper wire (confirming to IS-694: and latest amendments) without control switch shall be fixed on the existing plastic sheet/ gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet (Page No -5, Item No 2.2.1, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Point	0.00	160.00	Rupees One Hundred Sixty Only
106	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0 sqmm (Earth wire) FRLS multi strand PVC sulated copper wire (confirming to IS-694: and latest amendments) with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. completefor each outlet (Page No -5, Item No 2.2.2, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Point	0.00	250.00	Rupees Two Hundred Fifty Only
107	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0 sqmm (Earth wire) FRLS multi strand PVC sulated copper wire (confirming to IS-694: and latest amendments) with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. completefor each outlet (Page No -5, Item No 2.2.3, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Point	0.00	375.00	Rupees Three Hundred Seventy Five Only
108	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. (Page No -5, Item No 2.3.2, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Mtr	0.00	20.00	Rupees Twenty Only
109	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. (Page No -6, Item No 2.3.3, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Mtr	0.00	32.00	Rupees Thirty Two Only
110	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. (Page No -6, Item No 2.3.4, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Mtr	0.00	45.00	Rupees Forty Five Only
111	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due Groove cutting in Brick/Stone/C.C wall. (Page No -9, Item No 3.4.1, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	95.00	Rupees Ninety Five Only
112	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due Groove cutting in Brick/Stone/C.C wall. (Page No -9, Item No 3.4.3, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	125.00	Rupees One Hundred Twenty Five Only
113	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due Groove cutting in Brick/Stone/C.C wall. (Page No -9, Item No 3.4.4, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender	Each	0.00	125.00	Rupees One Hundred Twenty Five Only
114	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.(Page No -9, Item No 3.5.1, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	110.00	Rupees One Hundred Ten Only

Scanned with CamScanner

	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.(Page No -9, Item No 3.5.3, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	175.00	Rupees One Hundred Seventy Five Only
	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.(Page No -9, Item No 3.5.3, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	200.00	Rupees Two Hundred Only
117	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. (Page No -10, Item No 3.6.1, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	70.00	Rupees Seventy Only
118	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. (Page No -10, Item No 3.6.2, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	95.00	Rupees Ninety Five Only
119	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. (Page No -10, Item No 3.6.3, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	105.00	Rupees One Hundred Five Only
120	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. (Page No -10, Item No 3.6.3, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	290.00	Rupees Two Hundred Ninety Only
121	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. (Page No -10, Item No 3.6.8, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	115.00	Rupees One Hundred Fifteen Only
122	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. (Page No -10, Item No 3.6.9, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	96.00	Rupees Ninety Six Only
123	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. (Page No -10, Item No 3.6.10, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	182.00	Rupees One Hundred Eighty Two Only
124	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. (Page No -10, Item No 3.6.11, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	162.00	Rupees One Hundred Sixty Two Only
125	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. (Page No -10, Item No 3.6.12, Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	79.00	Rupees Seventy Nine Only
126	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. (Page No - 27, Item No 5.17.1 Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	434.00	Rupees Four Hundred Thirty Four Only
127	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. (Page No - 27, Item No 5.17.4 Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	909.00	Rupees Nine Hundred Nine Only
128	Supplying and fixing regular MCB distribution boards on wall/ wood board / flush mounting using required clamps, bolts,nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure. (Page No - 28, Item No 5.18.3 Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	960.00	Rupees Nine Hundred Sixty Only
129	Supplying, fixing and wiring Electronic Trivector Meter (ETV) to 20Amps single phase Class-1 Accuracy with Temper Proof Energy Meter. (Page No -29, Item No 5.31 Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender document	Each	0.00	1150.00	Rupees One Thousand One Hundred Fifty Only
130	Supplying of 1440rpm heavy duty exhaust fan with bracket blades suitable to operate on 230V 50Hz, AC Supply complete. (Page No -46, Item No 7.2.1 Electrical PWD SR 2019-20) ---- All terms and conditions are as per tender	Each	0.00	2100.00	Rupees Two Thousand One Hundred Only

Scanned with CamScann